

## 40 C.F.R. § 63.1382

## **Emission standards.**

- (a) You must control emissions from each glass-melting furnace, rotary spin manufacturing line, and flame attenuation manufacturing line as specified in Table 2 to this subpart.
- (b) On or after July 29, 2015 to reduce emissions of hydrogen chloride and hydrogen fluoride from each existing, new, or reconstructed glass-melting furnace, you must either:
- (1) Require cullet providers to provide records of their inspections showing that no glass from industrial (also known as continuous strand, or textile) fiberglass, cathode ray tubes (CRT), computer monitors that include CRT, and glass from microwave ovens, televisions or other electronics is included in the cullet; or
- (2) Sample your raw materials and maintain records of your sampling showing that the cullet is free of glass from industrial fiberglass, cathode ray tubes, computer monitors that include cathode ray tubes, and glass from microwave ovens, televisions or other electronics.
- (c) Operating limits. On and after the date on which the performance test required to be conducted by §§ 63.7 and 63.1384 is completed, the owner or operator must operate all affected control equipment and processes according to the following requirements.

(1)

- (i) The owner or operator must initiate corrective action within 1 hour of an alarm from a bag leak detection system and complete corrective actions in a timely manner according to the procedures in the operations, maintenance, and monitoring plan.
- (ii) The owner or operator must implement a Quality Improvement Plan (QIP) consistent with the compliance assurance monitoring provisions of 40 CFR part 64, subpart D when the bag leak detection system alarm is sounded for more than 5 percent of the total operating time in a 6-month block reporting period.

(2)

(i) The owner or operator must initiate corrective action within 1 hour when any 3-hour block average of the monitored electrostatic precipitator (ESP) parameter is outside the limit(s) established during the performance test as specified in § 63.1384 and complete corrective actions in a timely manner according to the procedures in the operations, maintenance, and monitoring plan.

This document is only available to subscribers. Please log in or purchase access.

## Purchase Login