40 C.F.R. § 63.9800

How do I conduct performance tests and establish operating limits?

(a) You must conduct each performance test in Table 4 to this subpart that applies to you.

(b) Before conducting the performance test, you must install and validate all monitoring equipment.

(c) Before May 19, 2022, each performance test must be conducted according to the requirements in § 63.7 and under the specific conditions in Table 4 to this subpart. On or after May 19, 2022, each performance test must be conducted under the specific conditions in Table 4 to this subpart.

(d) Before May 19, 2022, you may not conduct performance tests during periods of startup, shutdown, or malfunction, as specified in § 63.7(e)(1). On or after May 19, 2022, you may not conduct performance tests during periods of malfunction. You also may not conduct performance tests during periods of startup or shutdown. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. You must make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(e) You must conduct separate test runs for at least the duration specified for each performance test required in this section, as specified in § 63.7(e)(3) and Table 4 to this subpart.

(f) For batch process sources, you must satisfy the requirements specified in paragraphs (f)(1) through (5) of this section.